


Massachusetts Maritime Academy

Wind Turbine Project

Presented by
David A. Beck, P.E.
Jay Cashman, Inc.



Project Key Dates

- **Preliminary Technical Feasibility Study** by Sally Wright, PE - 21 May 2004
- DCAM Issues RFP in February 2005
- JCI Submitted Proposal March 9, 2005
- DCAM Awarded Contract July 2005
- Submitted Interconnect Application –Aug. 2005
- Order of Conditions Obtained Fall 2005
- Construction March and April 2006

Technical Feasibility Study

- UMASS RERL, Sally Wright
- Average wind speeds 6-6.5 m/s
- Fall Zone 1.5 x the blade tip height
- Setback from residences 3.0 x the hub height (492 ft. for V-47)
- Selected Site behind WWTP and Power Plant Building and next to Ball Field

Turbine Sitting



Vestas V47-660 kW Wind Generator Turbine

	meters	feet
Hub Height	50	164
Blade Sweep	47	154
Blade Tip Height	73.5	241

Post Cost and Saving

- Proposal Submitted at \$1.3M, Final \$1.4M
- Estimated CF = 25%; 1,461,746 kWh/year
- 82% used on Campus; 18% to grid @ \$.05
- Simple Payback without RECs = 7.5 years

- Assuming RECs at \$.05 per kWh, Simple Payback = 5.5 years


Project Design Team

- Jay Cashman, Inc. – General Contractor
- Energy Management, Inc. – Management Support
- ESS Group – Permitting (NOI and FAA)
- Solar Design – BOP Electrical Design
- LeMessurier Consultants – Foundation Design



Permitting

- ESS reviewed potential environmental Impacts
- Notice of Intent Filing with Bourne Conservation Commission
- FAA Notice of Proposed Construction (>200')
- State facility not subject to local bylaws
- The Mass Building Code followed
- Avian Impact Analysis
- Post Construction Avian Study by MMA

BOP Electrical Design



WTG Foundation Design



- 16 PIFs (50 tons/20 tons)
- 30'x30'x 4' Base Mat
- 14' Dia. X 2' Pedestal
- 96 Anchor Bolts

Construction Subcontractors

- G. Donaldson Construction – PIF Install
- Fiore Construction (MBE) - Site and Foundation Work
- R. Reid Electric (MBE) – BOP Electric Equipment
- Mass Electric Construction Company - Electrical BOP and WTG Work
- Keystone Engineering (WBE)– WTG Installation
- Lighthouse Electric Construction - DAS

Site Work and Foundation Installation

- Install Erosion Controls
- Install 16 Pressure Injected Footings (PIFs)
- Foundation Excavation
- Mud Mat and Remove PIF Concrete
- Install Base Mat Rebars, Anchors and Conduits
- Install Foundation Pedestal
- Install Buried Conduits
- Backfill Operations

Site Prior to Construction



Installation of 16 PIFs



Excavation Around PIFs



PIFs and Mud Mat



Bottom Steel and 96 Anchor Bolts



Rebars, Anchor Bolts and Conduits



Base Mat Concrete (110 CY)



Conduits at Manholes (EMH#5)



Conduits to Electric Equipment



Backfilling Foundation and Duct Bank



03/29/2006

Pedestal Forms



V47 Components

Tower From North Dakota

- Bottom Tower Section
- Top Tower Section

Parts From Italy

- Nacelle
- Parts Container - Hub, Nose Cone, Controller
- Blades Container

Nacelle Arrives at Site



Unloading Parts Container



Tower Sections Arrive



Base Section Making Turn Into Site



Making Turn at Pump House



04/12/2006

Base Tower Installation

- Offload from Transport
- Install Electrical Cables
- Power Wash
- Install Rigging
- Upright
- Place on Foundation over 96 Anchor Bolts
- Grout Base
- Pretension 96 Anchor Bolts

Inside of Base Section



Electrical Preparation Work



Lifting Base Section



Up Righting Base Section



Swinging Base Section



Tower Rigging



04/12/2006

Setting Tower Base Section



Rotor Assembly on Ball Field

- Offload Blades from Shipping Container
- Set-up Elephants Foot on Ball Field
- Set Hub and Fiberglass Cone
- Install Three Blades

Offloading Blades



Setting Hub on Elephant's Foot



04/13/2006

Blade Pitch Linkage



Setting Nose Cone on Hub



04/13/2006

Install First Blade



04/13/2006

Bolting Blade to Hub



Tie-Down of Blades



04/13/2006

Install Blades onto Hub



04/13/2006

Completed Rotor



Rotor Tied Down and Ready for Lifting




Install Top Section, Nacelle and Rotor (Friday April 14th)

- Install Cables in Top Tower Section
- Install FFA Lights and Wind Instruments on Nacelle
- Lift, Set and Bolt Top Tower Section
- Lift, Set and Bolt Nacelle
- Lift and install Rotor onto Nacelle

Rigging Tower Top Section



Lifting Top Tower Section



Up Righting Top Section



Lifting Top Section



Installing Top Section onto Tower Base Section



Setting Top Section



04/14/2006

Top Section Set



Derigging from Tower



Nacelle FAA Lights and Wind Vanes



Nacelle Preparation



Installing Nacelle Lift Chains



Nacelle Ready for Lifting



Lifting Nacelle from Transport



Lifting Nacelle From Transport



Lifting the Nacelle



Setting Nacelle on Tower



04/14/2006



Bolting Nacelle to Tower



Rotor Lift Rigging



Lifting Rotor from the Horizontal



Rotor Raised to Vertical



Rotor Hub





04/14/2006

Rotor Being Lifted



Man on Top



Rotor Mated to Nacelle



04/14/2006

Installation Completed

April 14th





Construction Schedule Summary

- March 15th – Start PIFs
- March 28th – Place Base Foundation
- April 10th – Nacelle Arrives at Site
- April 12th – Install Tower Base Section
- April 14th – Install Top, Nacelle and Rotor
- April 15th – WTG Electrical Hookup
- May 27th – Nstar Installs Recloser
- June – WTG Commissioning



Electrical Interconnection

- Application Submitted Aug. 2005
- Nstar Impact Study Completed Nov. 2005 (fee \$7,250)
- Jan. 2006 Advises Cost to Change out 65T Fuses with Recloser
- Feb. 2006 MMA pays Nstar for Recloser (about \$57,000 for additional protection)
- May 27, 2005 Nstar Installs Recloser

Questions?

